

VILLAGE OF VICTOR

INCORPORATED 1879

MAYOR

John S. Holden
924-3311

DEPUTY MAYOR

Tim Maher

BOARD OF TRUSTEES

Larry Rhodes
Gary Hadden
Tim Acquilano

VILLAGE CLERK

Pamela Hogenes

TREASURER

Diane White

VILLAGE ATTORNEY

Reid A. Holter

DIRECTOR OF PUBLIC WORKS

John C. Turner
924-2004

CODE ENFORCEMENT OFFICER

Alan Benedict
742-5035

PLANNING BOARD**CHAIRPERSON**

Meg CHaides

ZONING BOARD CHAIRPERSON

Michael Crowley

EXECUTIVE DIRECTOR LOCAL DEVELOPMENT

Kathy Rayburn
742-6320

Dear Residents:

As some of you are aware, Church Street is scheduled for reconstruction starting in the Spring of 2010. This is expected to be a two (2) year project.

The first phase of the project will be to replace the water and sewer via a bidding process. For the second year, the Village of Victor Department of Public Works will install new gutters, drainage, sidewalks and asphalt pavement.


We are currently doing a tree study to see what trees need to be removed for this construction and which ones can be saved. The Village Board of Trustees will be scheduling a public hearing to provide details of the project to the residents and hear their concerns.

The purpose of this letter is that a house by house inspection is necessary to locate sewer laterals and check water service for the construction. I would have to enter your home to inspect what type of material your home has.

Please call the Village Hall at (585) 924-3311 between the hours of 8:30am – 4:30pm to schedule an appointment. The appointments would be scheduled between the hours of 7:00am – 3:30pm and would be approximately 15 minutes.

Your cooperation with this project is greatly appreciated.

Sincerely,



John C. Turner,
Director of Public Works

**Informational Meeting Agenda for the
Village of Victor
Church Street Reconstruction
December 21, 2009**

Introductions:

John Paul Schepp	Chatfield Engineers
Tim Rouse	Chatfield Engineers
Andrew Pleninger	Urban Forestry

Chatfield Engineers has been Village Engineer since 1994 (16-years)
Church Street Reconstruction has been in various planning stages since 1998.
Church St. Water Mains were let for bids in 2001 – but rejected due to high cost.

Scope of Work:

Water Main Replacement (by Contactor)

East Parkway to Main Street
Increasing 4 & 6 inch cast iron mains with 8-inch
Replacing fire hydrants, valves and services to the R.O.W. at each home.

Sanitary Sewer Replacement (by Contactor)

Hillcrest to Main Street
Replacing 8-inch Vitrified Clay Tile with 8-inch PVC
Replacing manholes and laterals to the R.O.W. at each home.

Drainage Improvements (by DPW)

Village Line to Main Street
Replacing patchwork of piping and open ditches
Installing catch basins, manholes and HDPE Piping 12 to 18-inches
Tie-in at Main Street and at 151 Church Street

Sidewalk Replacement (by DPW & Subcontractor)

Hillcrest to Main Street

Road Replacement (by DPW & Subcontractor)

Village Line to Main Street
Install gutters Village Line to Andrews Street
Install curbs Andrews Street to Main Street
Right turning lane onto Main Street (3 -4 cars deep) Subject to DOT approval
New Roadway to include 2-12' wide lanes (one in each direction)

Total Estimated Project Costs: \$2.2 Million

Schedule: Final Plans and Approvals..... Winter 2009
Water Main & Sewer Construction..... Spring – Summer 2010
Drainage, Road & Sidewalk..... Summer – Fall 2010, complete Spring 2011

Tree Protection, Removal & Replacement: Andrew Pleninger

Questions & Comments:

